



GENERAL NOTES:

1. TRASH WILL BE COLLECTED IN THE TRASH DUMPSTER WITHIN THE EXISTING TRASH ENCLOSURE AREA.
 2. AREA OF WOODLAND R/D THAT IS NOT THRYING WILL BE RESEDED.
 3. ADD NEW TREES TO REPLACE DISEASED OR DEAD TREES.
 4. ADD PRESERVATION FENCING AS NECESSARY TO PROTECT SHRUBS CLOSE TO BUILDING FOUNDATION.
 5. ALL GROUNDS AND BUILDING MOUNTED UTILITIES AND EQUIPMENT WILL BE SCREENED FROM VIEW AS REQUIRED BY UDD 18.30.30.1. ANY ELECTRIC AND GAS METERS SHALL BE PLACED ON THE NORTH SIDE OF THE BUILDING.

(DETAILS)

 13. CONTRACTOR SHALL STAKE ALL PLANT MATERIALS PRIOR TO INSTALLATION FOR THE PURPOSE OF DETERMINING CONFLICTS WITH ROCK, UTILITIES, ETC. NO PLANTS CAN BE PLANTED DIRECTLY ON ROCK OR UTILITIES. NOTIFY ARCHITECT/ENGINEER/OWNER AT ONCE IF ANY CONFLICTS OCCUR.
 14. CONTRACTOR WILL BE REQUIRED TO ADJUST PLANT LOCATIONS AT NO ADDITIONAL COST.
 15. CONTRACTOR IS RESPONSIBLE FOR WATERING ALL 500 UNTIL ROOTS HAVE KNITTED INTO SOIL, AND OWNER HAS OCCUPIED THE BUILDING.
 16. PROVIDE "GATOR" BAGS ON ALL TREES, AFTER, AS NECESSARY UNTIL OWNER OCCUPIES THE BUILDING. BAGS TO REMAIN FOR USE BY OWNER.
 17. AREAS TO RECEIVE NATIVE SEED MIX SHALL HAVE SHORT LIFE (3-6 MONTHS) DURATION JUTE MESH BLANKET.
 18. ALL MECHANICAL EQUIPMENT, INGROUND AND BUILDING MOUNTED, SHALL BE SCREENED PER PERMITS REQUIREMENTS.

LANDSCAPE REQUIREMENTS

[illegible]

PLANT SCHEDULE

KEY	QTY.	BOTANICAL NAME	COMMON NAME	SIZE/REMARKS
DECIDUOUS TREES				
CSL	---	ACER SACCHARUM 'AUTUMN SPLENDOR'	CADDY SUGAR MAPLE	2.5" CAL. B&G
HM	---	LEDITISA TRIACANTHOS 'SKYLINE'	SKYLINE HONEYLOCUST	2.5" CAL. B&G
RO	---	QUERCUS RUBRA	RED OAK	2.5" CAL. B&G
BC	---	TAXODIUM DISTICHUM	BALDYPRESS	2.5" CAL. B&G
RB	---	CERES CANADENSIS 'OKLAHOMA'	OKLAHOMA REDBUD	1.5" CAL. B&G
SS	---	MALUS 'SPRING SNOW'	SPRING SNOW CRABAPPLE	1.5" CAL. B&G
EVERGREEN TREES				
SJ	---	JUNIPERUS CHINENSIS 'SKYROCKET'	SKYROCKET JUNIPER	6' HT.
NS	---	PICEA ABIES	NORWAY SPRUCE	6' HT.



