

Custom Cut Metals, Inc.

2214 Front St.  
Kansas City, KS 66101

## Quote

DATE	Quote #
2/24/2020	5086

BILL TO
City of Olathe Parks and Public Grounds 400 N 7 Hwy Olathe, KS 66061

SHIP TO
Library 16100 W 135th St Olathe, KS

P.O. NO.	TERMS	PROJECT
	Net 30	

DESCRIPTION	QTY	RATE	AMOUNT
Aluminum Trellis Fabrication; alum tube frame and lattice; connecting brackets and hardware	1	54,000.00	54,000.00T
Powder Coating; sand blasting and clear powdercoat finish of above items (unable to guarantee for 5 years, but certainly expected to last that long)	1	16,000.00	16,000.00T
Delivery to powdercoater, then to jobsite	1	800.00	800.00T
Lattice pannels to be fabricated out of 3/8" x 2" bar stock; then welded to partial subframe tubing, which will then be field installed to 6 column pannel frames using 3" welded angle w/ alligned holes in adjoining column frames. Powdercoaters would not guarantee 5 years. We will get samples for approval of sandblasted/ clear coat before proceeding. Lead time to acquire material, fabricate and powdercoat approx. 7 to 9 weeks from approval of project.			
Custom Cut Metals is committed to the success of this projetct and will work closely with architects and engineers when needed. Sales Tax , this job is non taxable, cert on file		0.00	0.00

Thank for allowing us to quote your business.